

ENGINEERING PROJECT — C2

CONTRACT DOCUMENT

CONTRACT NUMBER: VG-CP2-CIV-
CAL-0037

DOCUMENT TITLE: Foundation Loading
Analysis — Area 300

REVISION NUMBER: Rev A

ISSUE PURPOSE: IFR — Issued for
Review

SECURITY CLASSIFICATION: Company
Use

DOCUMENT TYPE: CAL — Calculation

DISCIPLINE CODE: CIV — Civil

DOCUMENT DATE: 02 April 2026

FROM ORGANISATION: WOR — Worley
Group Pty Ltd

PROJECT: Engineering Project — C2 EPC-
BOP

ENGINEERING PROJECT — C2

DOCUMENT CONTROL INFORMATION

SECOND COVER PAGE — DOCUMENT CONTROL INFORMATION

SDx Project Area: C2
Contract Reference: C2 EPC-BOP

Prepared by: H. Tanaka Date: 02-Apr-2026
Reviewed by: F. Al-Rashid Date: 03-Apr-2026

REVISION HISTORY

[illegible]

1. INTRODUCTION

This calculation report presents the foundation loading analysis for Area 300 under Contract C2 EPC-BOP. All calculations follow IBC 2021 and project specification VGL-CIV-STD-004.

[COMMENT] Reviewer F. Al-Rashid:

Please double-check the soil bearing capacity assumption of 150 kPa — geotechnical report indicates 120 kPa for this area.

[MARKUP] Section 2.3 highlighted for further review by structural team.

/Annots [<< /Type /Annot /Subtype /Text /Contents (Need to verify load case LC-04 against seismic criteria) >>]

2. DESIGN INPUTS

Soil bearing capacity: 150 kPa (assumed — pending geotechnical confirmation)
Seismic zone: Zone 2A per IBC 2021
Foundation type: Isolated pad footings with grade beams
Concrete grade: C40/50 (40 MPa cylinder / 50 MPa cube)

3. RESULTS

All foundations satisfy the required safety factor of 2.5 under combined loading.
Maximum settlement: 12mm (allowable: 25mm).

